VENDOR NAME: SBC SNET FEIN: 06-054-26-46

SERVICE/PRODUCT NAME: ATM and Frame Relay Service - Frame Relay Service

SERVICE/PRODUCT DESCRIPTION:

Frame Relay Architecture

Frame relay uses high quality, digital transmission facilities and advanced packet switching technology to provide a connection oriented high-speed service. Connection oriented simply means that data transmissions (frames or segments of end user data) sent through the frame relay network always follow the same pre-defined path with the data arriving in the order it was sent. This type of service allows for the transfer of variable length frames across a wide geographical area.


An access link to the Frame Relay Service is provided through digital access facilities between a customer's premise and a frame relay node (switch port). A virtual connection or logical link between customer-selected access links is established within the frame relay switch through a software defined logical connection (PVC). Data Link Circuit Identifiers (DLCIs) are numerical address assignments for the end-points. The combination of an access link, logical link, and DLCIs allows real time dynamic allocation of switch capacity.

With frame relay, customers can cost-effectively provide a high level of direct connectivity between remote locations. Once a single physical connection into the network is established, additional logical connections can be added at a relatively low cost. By providing a greater level of direct connectivity between locations, nearly all network users benefit. Network congestion is reduced at the primary location and network response times are reduced.

The intelligence inherent in a frame relay network results in the ability to automatically route PVCs around a network failure. Depending upon current network architecture and the amount of redundancy already built into the network, this capability can help to increase overall network availability. Because many logical connections share the same physical interface into the frame relay network, the number of local loops needed is often reduced significantly.

Frame Relay service allows the customer to exploit the intermittent characteristic of data by oversubscribing the port connection. Oversubscription means that the customer can actually assign more PVCs and total Committed Information Rate (CIR) to a port than the port connection speed.

Frame to ATM Interworking provides a smooth and seamless migration from frame relay to ATM on a per site basis as the connectivity needs of an individual site change and grow. One or two network sites can be upgraded to ATM without affecting the rest of the network. The network provides the protocol conversion.



SBC SNET Product Offerings

Access Links (Physical circuit connection from the customer location to the serving Frame Relay Switch)

- DS0-56 kbps
- DS0-64 kbps
- 128 kbps
- 256 kbps
- 384 kbps
- 1.544 Mbps.

Permanent virtual circuits (PVCs)

- PVCs are provisioned in increments of 4 kbps with a minimum setting of 4 kbps
- The maximum allowable committed information rate (CIR) setting for any single PVC is 50% of the port speed: 56, 64, 128, 256, 384 kbps and 1.544 Mbps
- 300% oversubscription is allowed

SERVICE LEVELS:

Installation Intervals

Less than 10 circuits (includes port and access link) = 20 business days 10 or more circuits = Individual Case Basis

PVC only = 5 business days

PVC or CIR change = 3 business days

Routine Repair Intervals

Response time = Less than 1 hour Repair Resolution time = 4 hours or less

Repair Service Level Definitions:

Repair Response is the time elapsed between when SNET receives a report of a problem or otherwise becomes aware of a problem, and the time that SNET responds to the end user or other designated contact to verify the problem.

Repair Resolution Time means the elapsed time between when the State notifies SNET of a problem, and the time that SNET restores service and such service is acceptable to the State.

SERVICE AVAILABILITY/LIMITATIONS:

SERVICE AVAILABILITY

See Service Availability spreadsheet

PROVISIONING PARAMETERS

FRAME RELAY TO FRAME RELAY				
Port Speed	CIR	Policing Graceful Discard OFF	Bc (Kbps)	Be(Kbps)
56K	28Kbps	enabled	28	28
64K	32Kbps	enabled	32	32
128K	64Kbps	enabled	64	64
256K	128Kbps	enabled	128	128
384K	192Kbps	enabled	192	192
1536K (T-1)	128Kbps	enabled	128	1408
1536K (T-1)	256Kbps	enabled	256	1280
1536K (T-1)	384Kbps	enabled	384	1152
1536K (T-1)	512Kbps	enabled	512	1024
1536K (T-1)	768Kbps	enabled	768	768

Notes:

- Policing will apply on a per PVC basis.
- The policing option will be enabled on new PVCs and any moves, adds or changes to the PVC or circuit. This includes repointing a PVC or changing the speed of the circuit.
- Policing will remain disabled (Graceful Discard ON) on PVCs in place today that are unchanged.
- Be = Line Rate CIR
 - (Burst excess will be set to the lowest line rate minus the CIR)
- 300% oversubscription is allowed.

5/6/2004 **DOIT APPROVAL DATE:** MASTER AGREEMENT NUMBER: B-03-006 VENDOR NAME: **SBC SNET** VENDOR FEIN: 06-054-26-46 ATM and Frame Relay Service - Frame Relay SERVICE NAME: A 2% credit will be issued monthly against the items ordered from this Product Schedule per the SBC SNET Master Agreement Initial Post-Activity Date of Date Item Conversion: Conversion: Recurring (Add, Vendor Approved Item Description of Service/Equipment Unit Delete, Code Non-Recurring Non-Recurring Monthly Cost Request By DOIT **Unit Cost** Change) **Unit Cost** FRAME RELAY Port and port + 10/08/03 Access Link DS0 acc link \$0.00 \$0.00 \$117.00 Add 10/10/03 1 FRAME RELAY Port and port + Access Link 128k \$0.00 \$0.00 \$300.00 Add 10/08/03 10/10/03 2 acc link FRAME RELAY Port and port + Access Link 256k Add 10/08/03 10/10/03 3 acc link \$0.00 \$0.00 \$360.00 FRAME RELAY Port and port + Access Link 384k acc link \$0.00 \$0.00 \$405.00 Add 10/08/03 10/10/03 4 FRAME RELAY Port and port + Access Link DS1 \$0.00 \$0.00 \$415.00 10/08/03 10/10/03 acc link Add 5 FRAME RELAY PVC pvc w Ordered with Port \$0.00 \$0.00 \$6.00 Add 10/08/03 10/10/03 6 port FRAME RELAY PVC pvc w/o Ordered without Port \$0.00 \$0.00 \$6.00 port Add 10/08/03 10/10/03 7 FRAME RELAY Change

link

port +

pvc

acc link

\$0.00

\$800.00

\$0.00

\$0.00

\$800.00

\$0.00

\$0.00

\$336.00

\$9.00

Access Link Speed

128k

Relay PVC

Woodbury Area- Frame Relay Port and Access Link

Woodbury Area- Frame

8

9

10

10/10/03

05/06/04

05/06/04

Add

Add

Add

10/08/03

04/05/04

04/05/04